

<b>Object</b>	<b>M/V Paul Tregurtha</b>
Project	<b>Colt-Pielstick Diesel 16 PC2-3V-400</b>
Place	<b>Naticoko, Ontario</b>
Date of installation	<b>2003</b>
Building Authority	<b>Fairbans Morse Beloit</b>
Planner	
Building Contractor	<b>Tadco Manufacturing Inc.</b>

Type of line	Air in take manifold
Product	<b>STRAUB-REP 2LS</b>
Diameter Ø	388.23 mm
Sealing sleeve	<input type="checkbox"/> EPDM <input checked="" type="checkbox"/> NBR
Casing	
Lock parts	<input checked="" type="checkbox"/> Stainless steel <input type="checkbox"/> galvanized
Working pressure	3 bar
Test pressure	5 bar
Remarks	

<b>Situation:</b>	Leaking pipe connections on air intake
<b>Solution:</b>	STRAUB-REP 2LS
<b>Customer benefits:</b>	Easy installation and servicing



Two Pielstick Engines  
16 Cylinders

